BRUHAT BANGALORE MAHANAGARA PALIKE

Yelahanka Zone, Electrical Division

Name of Work:-Detailed Estime forReleased Tubular Pole along with street lights to sampegehalli Police Station to Chokkanahalli village Main Road in ward No 05

Budget Head :P0298 M&R

Ward No. 05 Estimate No:-35/16-17 For Rs. 200000.00

Sl No	SR Page & SL No	Description Of Work	Qty	Rate	Unit	Amount
	KPWD (Ele) S.R.2014-15					
1	56/7 6 1	Supplying of 1.1KV grade Aerial Bunched Cable Stranded & Compacted Aluminum Phase Conductor, and Stranded Messenger Conductor with all aluminum Alloy, Phase Conductor is insulated with XLPE Compound, insulated Messenger with specified IS-14255:1995 & confirming to GTP of GROUP-A 2 X 16 + 1 X 25 SQ.MM	425	92 00	Per Mtr	39100.00
2	56/7 6 3	3 X 16 + 1 X 25 + 1 X 16 SQ.MM	1000	117.00	Per Mtr	117000 00
3	33/5 4 2	Supply and fixing of ..... cross arm including all Hardware's complete as per the standard technical specification of BESCOM 2 Pin 45x45x5mm -510mm	28	306.00	Each	8568.00
4	Bes SR	Stringing of 1.1kv LT Arial Bunched Cable, BESCOM SR	1425	10.30	Per Mtr	14677.50
4	Bes SR	Dead End Clamp/Anchor Clamp Assembly 16 to70 Sqmm Bare Messenger(Exclusive of pole clamp and eye hook) (Standard Stock materials 2016-17)	7	200.00	Each	1400 00
5	Bes SR	Suspension clamp suitable for insulatedMesssenger wire of size 25 to 95Sq mm(Standard Stock materials 2016-17)	40	325.00		13000.00

6	Bes SR	Erection of Suspension /dead end Clamp - 25 to 95insulated messenger with bracket sqmm(Standard Stock materials 2016-17)	46	135 00		6210 00
7		Miscellaneous				44.50
		TOTAL				200000.00

CERTIFICATE :-

1. The place was inspected and the work is essential.
2. The provision made in the estimate are adequate and necessary and the work comes in the BBMP limit and is legitimate Charges on the BBMP funds.
3. The estimate is based on KPWD (Ele) S.R.2014-15 Rates and BESCOM SR 16-17.

Asst. Engineer (Elec)

Asst. Executive Engineer (Elec)
Sub-Division No
Bruhat Bangalore Mahanagara Palike

EXECUTIVE ENGINEER (ELEC)
YELAHANKA DIVISION
BRUHAT BANGALORE MAHANAGARA PALIKE

Administrative Sanction for Rs. 2.00 Lakhs
Two Lakhs only
is accorded under PD208 M&R to Electrical Installation in parks
PS
Registered as EE No. EE/ELE/42/21/16-17
to conditions contained in enclosed memo
No. PND-5H255 dt:-20-2-17

Executive Engineer

TECHNICALLY SANCTIONED FOR Rs. 2.00 Lakhs
Rupees Two Lakhs only
Under PD208 M&R to Electrical Installation in parks
Registered as EE ( ) No. EE/ELE/42/T3/22/16-17
Subject to conditions contained in
enclosed memo EE ( ) No. PS/EE-21/16-17
Dt. 20-2-17 Estimate A/c Sanctioned
No. PND-76&77
Dated 22-2-17 Rs. 2 Lakhs

Executive Engineer